



Commissioning the Zimplats Smelter Expansion & SO₂ Abatement Project

Setting the benchmark for future PGM smelting projects



HATCH

Project Overview




Overview and Purpose

Triple smelting capacity to support growth and third-party concentrate toll treatment




Location and Industry Impact

Selous Metallurgical Complex
Zimbabwe



Partnership and Timeline


Hatch managed engineering, procurement, and construction; commissioning began July 2024 with matte tap in October 2024.




Collaborative Achievement

Successful first matte tap marks achievement of client's schedule and long-term collaboration since 2002.

Pre-expansion setup



Expansion scope



Design Considerations



Independent Operation Design

- Operate independently from the existing smelter
- New utilities (compressed air, cooling water, etc.)
- Extended converter aisle


Off-Gas Handling System

- Primary and secondary off-gas systems
- 160 m tall concrete stack
- Hot bypass to minimize disruption during tie-ins and shutdowns.

Future Infrastructure Preparedness

- Infrastructure was prepared for deferred projects like the SMC Base Metal Refinery upgrade and SO₂ Abatement Plant installation.


Timelines Highlights



Overlapping design, construction and commissioning
□ *Significant integration & collaboration between teams*

Commissioning Sequence

Priority ☐ furnace start-up readiness




		Jun	Jul	Aug	Sep
1	Furnace substation	MV Energized	LV Small Power Energized	LV MCC Energized	
2	Acid plant substation	LV Small Power & Network Commissioned	MV Energized	LV MCC Energized	
	Converter substation	LV Small Power & Network Commissioned	MV Energized	LV MCC Energized	
	Control room	Control Room Operational			
3	Compressed air		Compressed Air Commissioned		
4	Concentrate feed		Flash Dryer and Concentrate Transfer Commissioned		
5	Water		Water Systems Commissioned		
			Central Cooling Water Plant Commissioned		
	Furnace commissioning (S1 - S3)		Furnace Refractory Complete	Furnace Systems Commissioned	
5	Furnace start-up		Slag Granulation Commissioned	Furnace - Heat-up	Furnace - Power On
					Slag Addition
					Concentrate Feed
					First Slag Tap
					First Matte Tap

Depending on construction progress in a specific areas, some systems were partially commissioned before formal handover.

Commissioning in a fast-paced environment

16 July - 17 August 2024

6,707 check sheets completed by construction and commissioning teams



Check sheets

- S1: 5,143
- S2: 4,192
- S3: 33

Equipment

- +3,000 new IO
- 11 new PLCs and their SCADA integration
- 3 new substations

Teams

- ~70 Hatch employees (construction, commissioning and start-up)
- Zimplats instrument technicians and operational personnel
- OEM equipment vendors (flash dryer, converters)

Success-recipe

- Close collaboration between teams
- Daily check sheet tracking using online system

Commissioning Challenges & Solutions

Fast-tracked schedule



Managing scope changes

Inevitable late design changes due to:

- Fast-tracked project schedule
- Proactive risk-taking
- Operator involvement and updated information influenced several design modifications

Implementation of changes during ongoing construction and commissioning activities.



Adapting for Deferred scope

Shared utilities between smelter expansion and SO₂ abatement plant:

- 60% of cooling water requirement by SO₂ abatement plant
- Largest impact on off-gas system and control



Managing Handovers

Overlapping phases and concurrent operation of both furnace = capacity of operators to be involved with cold commissioning was limited

Commissioning Challenges & Solutions

+ Ramp-up and Optimisation (case study)



Furnace slag transfer system

Fibers / angel hair in granulated slag

Interim manual removal required

Reviewed chemical and physical properties

Adopted changes □ improvements



Project Success

Fast-tracked execution

- Feasibility in 2021 □ Hot commissioning by Dec 2024 (4 years)
- Integration across design, construction, and commissioning □ smooth project progress and quality outcomes.

Collaborative Partnership

- Collaboration between key partners was critical in managing scope changes and meeting tight deadlines effectively.


Adaptive Focus

- Maintaining adaptability and focus on core objectives enabled timely completion and achievement of performance targets.


Strategic Planning

- Strategic planning and teamwork formed the foundation for the project's successful completion and achievements.

Benchmark for future PGM smelting projects



Copyright © Hatch 2025. All rights reserved.1



Contact us at:

Minet.Crafford@hatch.com
Meshack.Monobe@hatch.com
Stanley.Matutu@zimplats.com
Gert.Erasmus@hatch.com



*Scan here for a copy of the paper
and other interesting material*